

To,  
**The Principal,**  
**Oriental Insurance Training College,**  
**Mathura Road, Faridabad.**

**Sub: Our Best Rates for Installation and Commissioning of  
 120 KVR Capacitor Bank**

**Dear Sir,**  
 With regard to installation of 120 KVAR Capacitor Bank penal at your training college premises which would operate automatically in 8 steps/sets with the variation of load, our best rates are as detailed under.

3 sets of 20 KVAR Capacitors = 60 KVAR  
 2 sets of 15 KVAR Capacitors = 30 KVAR  
 3 sets of 10 KVAR Capacitors = 30 KVAR  
 1 sets of 10 KVAR Capacitors = 10 KVAR

S.no	Material Required	Qty. (In Nos.)	Make	Rate per unit	Total Cost
1	MCCB 300 ATP	1	L&T		
2	Digital Meters	3	L&T,		
3	Auto P.Factor Control Relay (8steps)	1	L&T,		
4	Penal Encloser With Aluminum Bus & Hardware etc.	1	MS Sheet 20 S.W. gauge		
5	<b>For 3 sets of 20 KVAR Capacitors</b>				
	a. MCB 63 Amp.	3	L&T,		
	b. Contractor Amp.	3	L&T		
	c. Push Button, Light Indicators, Wiring & Hardware etc.	3	Siemens		

6	For 2 sets of 15 KVAR Capacitors	a. MCB 40 ATP	2	L&T,		
		b. Contractor	2	L&T,		
		c. Push Button, Light Indicators, Wiring & Hardware etc.	2	Siemens		
7.	For 2 sets of 10 KVAR Capacitors	a. MCB 32 ATP	2	L&T		
		b. Contractor AMP, TP	2	L&T		
		c. Push Button, Light Indicators, Wiring & Hardware etc.	2	Siemens		
8.	1 Number 10 KVAR Capacitor for T/F Direct			Siemens		
9.	MCB 32 ATP	1	L & T			
10.	Contractor and Wiring etc.	1	L & T			
11	Capacitor 10 KVAR each	11	Siemens			
12	Capacitor 5 KVAR each	2	Siemens			
13	20 Meter Cable 120mm <sup>2</sup> 3.5 core along with cable box & terminal ends	20 meters	Havells			
14	Platform channel attached with panel	1	MS 4 inch wide			

15	Current Transformers (CTs 3 + 1)	4	L & T		
				Total	
16				Add Excise	
17				Add VAT	
18				Add: Any other Taxes ( give details )	
19	Total cost of equipments / parts with all taxes as applicable				
20	Add : Installation, Commissioning , Transportation including Service Charges or any other charges				
21	Add : Service Tax, if applicable				
22	Grand Total ( for total cost on turnkey basis for installation/ commissioning and handing over of the Capacitor bank to OSTC ). No other charges are payable under any circumstances.				

Note:

- Vendor may inspect the site to familiarise with the proposed work.
- Brand/ Specification of material to be used for the above panel should be as per details above
- Inspection of all Material/ units by your designated engineers shall be arranged before dispatch / installation of the same.
- One year Warranty along with free maintenance and service of the panel would be provided by us.
- Rates Quoted shall be valid for 120 days.
- After confirmed order, the installation will be completed within 30 days.

Manufacturer/ Supplier Signature Stamp, address and  
phone no.